BRUHATH BENGALURU MAHANAGARA PALIKE

EXTRA ITEM RATE LIST (EIRL)

Name of Work: Restoration and Improvements of Roads at Hesaraghatta Main road, G Ramaiah layout, Sai Archadc layout, Vijaya bank layout, Adityanagara Phasc-02, and Surrounding arcas in ward no-03 of Yelahanka New town Sub-division

BRUHAT BANGALORE MAHANAGARA PALIKE

Name of the Work : Restoration and Improvements of Roads at Hesaraghatta Main road, G Ramaiah layout, Sai Archade layout, Vijaya bank layout, Adityanagara Phase-02, and Surrounding areas in ward no-03 of Yelahanka New town Sub-division

EXTRA ITEM RATE LIST (EIRL)

Sl No	Item Of Work	Unit	Estimate Qty	Rate in Rs. Considering 2018-19 PWD SR	Amount (Rs.)	Whether the item alternative in tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R.	Remarks
1	2	3	4	5	6	7	8	9	10	11
EIRL-1	Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications. KSRB 14.6-1 : -d o - heavy duty cobble stones 75mm thick (14.6.2/103)	Sqm	350.61	1188.37	416653.00	Additonal Item	No	Savings Amount	Yes, KSRRB Item No-14.6.2 Page No 103	
	TOTAL EIRL AMOUNT				416653.00					

PERCENTAGE OF EXCESS COMPARING TO SANCTIONED COST $\frac{416653.00}{101628317.00} \times 100 = 0.41\%$

Assistant Engineer
Ward No.03
BBMP-Bangalore

Assistant Executive Engineer
Yelahanka New Town Sub-Division
BBMP-Bangalore

Executive Engineer
Yelahanka Division
BBMP-Bangalore

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ